

NETAJI NAGAR DAY COLLEGE

(Under Graduate & Post Graduate Institute)

Affiliated to University of Calcutta

Accredited by NAAC (B+)

170/436, N. S. C. BOSE ROAD

REGENT ESTATE, KOLKATA - 700 092

Ref. No ..NNDc/7/6/2016.

Date ..22. 11. 2016

Tender for Carpentry and Interior works

1.Partition

(a) **Existing Partitions:-**Remodeling existing partition-Providing and fixing low height solid partition upto 1200mm height. The partition framework to be covered with 6mm thick plywood and finished with 1.0 mm thick laminate. wood binding to be provided at the edge of the partition finished with approved shade of polish or paint.

Qty: 180.00 Sq.ft.

2. Storage cabinet

(a) **EXISTING Full Ht storage-REMODELING:-**

Providing and fixing full height storage unit (2100 mm high) Inside paint finished and 1.0mm thick laminate externally. If required hardwares all complete hinges,handles,locks etc.

i.2 shutter size of storage (7'-6"x3'-0") 2 no unit : qty; 45.00 sqft

ii.2 shutter size of storage (6'-0"x3'-0") 2 no unit: qty; 18.00 sqft

(b) **Low Ht storage or overhead storage (EXISTING)**

Same as item 2 a-(i) above but low height storage unit upto 750mm height with openable/sliding shutters and locking arrangement.

i)8 shutter size of storage (9'-6"x 3'-0") 2 no unit :qty; 57.00 sqft

ii) 4 shutter size of storage (6'-6"x 3'-0") 2 no unit :qty; 39.00 sqft

(c) **Low Ht storage or overhead storage (NEW)**

Same as item 2 a-(i) above but low height storage unit upto 750mm height with openable/sliding shutters and locking arrangement.

i)6 shutter size of storage (8'-0"x 3'-0") 2 no unit :qty; 24.00 sqft

ii) 4 shutter size of storage (5'-0"x 3'-0") 2 no unit in cash cabin:qty; 15.00 sqft


3. Tables

(a) **Existing Front Table- REMODELING**

(i) Providing and fixing in place, Officer's table of size existing size in addition and one drawer & one shutter & Table top with comprising of 6 mm thick ply of all side of the table. All complete including necessary hardwares. All the external surface to be finished with 1.0mm thick laminate and internal surfaces to be finished with paint of approved shade, all complete as directed.

Qty: 5 Nos.

SBGash
22.11.16



NETAJI NAGAR DAY COLLEGE

Phone : 2411-5301

(Under Graduate & Post Graduate Institute)

Affiliated to University of Calcutta

Accredited by NAAC (B+)

170/436, N. S. C. BOSE ROAD

REGENT ESTATE, KOLKATA - 700 092

Ref. No. NNDC/T/16/2016

Date 22.11.2016

(b) Staff Table wall side main counter-EXISTING REMODELING

(i) Double level counter made out of 19mm thick plywood and finished in laminate as per existing table. All the exposed surfaces to be finished with 1.0mm thick laminate and internal surfaces to be finished with paint (Pedestal), all complete hardware as per requirements to be followed.

Qty: 4 nos

(c) Staff Computer Table-EXISTING REMODELING

(i) Providing and fixing in place, Officer's table of existing size in addition and one drawer & one shutter & Table top with comprising of 6 mm thick ply of all side of the table. All complete including necessary hardware. All the external surfaces to be furnished with 1.0mm thick laminate and internal surfaces to be finished with paint of approved shade. all complete as directed.

Qty: 2 Nos.

(d) Staff Computer Table-(NEW)

(i) Providing and fixing in place, Officer's table of existing size in addition and one drawer & one shutter & Table top with comprising of 6mm thick ply of all the table. All complete including necessary hardware. All the external surfaces to be finished with 1.0 mm thick laminate and internal surfaces to be finished with paint of approved shade. all complete as directed.

Qty: 2 Nos

(e) Staff Computer Long Table-EXISTING REMODELING

(i) Providing and fixing in place, computer long table. All complete including necessary hardware. All the external surfaces to be finished with 1.0mm thick laminate and internal surfaces to be finished with paint of approved shade. all complete as directed.

Qty:1 Nos.

(f) Clark cabin Table-EXISTING REMODELLING

(i) Providing and fixing in place, 'L' type table of existing size in addition and one drawer & one shutter & Table top with comprising of 6mm thick ply of all side of the table. All complete including necessary hardware. All the external surfaces to be finished with 1.0mm thick laminate and internal surfaces to be finished with paint of approved shade. all complete as directed.

Qty:1 nos.

SB Jash
22.11.16



NETAJI NAGAR DAY COLLEGE

Phone : 2411-5301

(Under Graduate & Post Graduate Institute)

Affiliated to University of Calcutta

Accredited by NAAC (B+)

170/436, N. S. C. BOSE ROAD

REGENT ESTATE, KOLKATA - 700 092

Ref. No. NNDC/7/6-2016

Date 22.11.2016

(g) Head Clark cabin Table-EXISTING REMODELING

(i) Providing and fixing in place, table of existing size in addition Table top with comprising of 6 mm thick ply of all side of the table. All complete including necessary hardwares. All the external surfaces to be finished with 1.0mm thick laminate and internal surfaces to be finished with paint of approves shade. all complete as directed.

Qty: 1 Nos

(h) Cash cabin Table-EXISTING REMODELLING

(i) Providing and fixing in place, table of existing size in addition and one drawer & one shutter & Table top with comprising of 6 mm thick ply of all side of the table. All complete including necessary hardwares, all the external surfaces to be finished with 1.0mm thick laminate and internal surfaces to be finished with paint of approved shade. All complete as directed.

Qty: 1 nos.

4. Miscellaneous

(a) Soft/Pinup Board

(i). Providing and fixing 12thk. Soft board comparing of 12mm thk. Back ply fixed on wall with 12mm thk pinup board (soft board) covered with fabric of approved shade (Basic cost =Rs. 100 per running meter).

Qty:32 Sq ft.

b. Vertical Blinds

(i) Supplying and fixing 4" wide vertical fabric blinds of approved made and colour and texture including all fittings of approved quality complete. Blinds made using 100% polyester with acrylic polymer coating.

Qty:75 sq ft.

(c) Mirror for Toilets & Strong Room

(i) Providing and fixing flawless 6 mm thk. Mirror of approved quality. The mirror shall be fixed on 12mm thk marine plywood backing with stainless steel mirror screws.

Qty: 10 sq ft.

Last date of Quotation submission:30.11.2016

Quotation should be submitted at the office:11.00 A.M. to 3.00 of each working day except Saturday.

SBgash
22.11.16